

KALKASKA

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
		A-3	C-2
1. PUBLIC LAND SURVEY _____	T. <u>26</u> N. <del>26</del> R. <u>6</u> E. <del>W.</del>	B-3	C-3
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11-9 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-3 Accepted recovered corner as shown by local land owner.
- B-3 Accepted recovered corner.
- C-2 Accepted corner as recovered in N-S gravel road.
- C-3 Recovered corner of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3	B-3	C-2	C-3
Found old well point, Added DNR Map. & Ced. Guard Post	Fd. 1 1/2" pipe w/nipple	Set 1"x18" pipe over Fd. Well pt in line with fence to E & W.	Fd. 1/2" rered with R.L.S. Cap #14102
22" Hemlock S66W 72.0'	14" Maple N38W 31.7'	8" Maple S40E 50.00	p.P. N55W 56.86
6" Hemlock N55W 53.0'	12" Maple N 4W 52.6'	14" Maple N42E 93.69	p.P. S31E 48.06
22" W.Pine N50E 77.1'	Scth Pine 5' S51E 44.0'	P.P. S28W 79.49	(Cor Fen post S47W 56.25)
(Ctr E-W swamp rd Due N) 5.5'	(Ctr E-W Dirt Rd Due S) 3.5'		(In ctr of Co.Rd N-S-E-W.)


SIGNED BY Carl F. Roser DATE 11-1-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_