

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>26</u> N. <u>X</u> , R. <u>6</u> W.	E-11; E-13; F-11
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 2-9 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

### A. Description of original monument and accessories and/or subsequent restoration:

### B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-11 Recovered 1" pipe on river bank. Fence N-S-E-W, per Richards-Findorff-Richards survey of Sectbn 28, 1964±.
- E-13 Recovered concrete monument, rerod & 1" pipe, Fence N & W, per Richards, Findorff, Richards survey of Sec. 32, 1964±. Equals Fargo recovered corner in 1913.
- F-11 Recovered concrete monument by corner fence post (Fn. W & N) per Richards, Findorff, Richards survey of Sec. 28, 1964±.

### C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11			E-13			F-11		
Found 1" pipe			Fd. Conc. Mon w/loc tag on Cor. Fn. Post			Fd. Conc. Mon. Added Cedar Gd. Post w/loc tag		
5" Thornapple	S47E	41.6	6" Cherry	S11W	45.5	6" W. Birch	N40E	68.4
8" Tw Ash	S15E	36.2	5" Maple	N70W	76.2	28" W.P. Stump	N35E	17.8
7" Ash	N84E	58.0	4" Maple	N15E	92.5	6" W. Birch	N86W	95.4
						E-W Random	Due N	15.7


SIGNED BY Carl F. Roser DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_