

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR 6 W

Kalkaska COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 15-16-21-22

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER


6" Cedar	-	N37E	-	42½ links
24" Elm	-	S47E	-	75 links
10" Maple	-	S50W	-	89 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by Forestry Division survey crew while making a partial resurvey of this township. Established corner by double proportionate measurement, using original corners ½ mile north and ½ mile south, and established corners 1 mile east and west. Falls about 10' north of centerline of E-W county road. All government evidence gone in road construction.

Corner was placed and witnessed 9/23/59.

SURVEYORS SEAL



SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE 9/25/59