

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 26 NR. 6 W.

Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15 & 16

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap.

WITNESSES TO CORNER

6" Cedar - N30E - 45 links

8" Cedar - N50W - 9 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a partial resurvey of this township. Set corner from what we conclude to be the NE government BT. This is a 9" Tamarack, down and partially rotted at the butt, having both faces and scribed 1/4 S and NBT. Appears to have grown 60 years after marking, by ring count, and was 120 years old when it stopped growing. Found a small stake point when digging at corner. A possible site for SW government BT. Can find no record of subsequent survey.

Corner was placed and witnessed December 4, 1957.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling  
REGISTERED LAND SURVEYOR

DATE 9-4-59