

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 NR. 6 W. ..

----- Kalkaska ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 14, 15, 22, 23 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 30" E. Pine Stump - N 47 E - 109 Links -----

36" E. Pine Stump - S 17 W - 100 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Corner was placed and witnessed May 16, 1952.

SURVEYORS SEAL

SIGNED *John C. DeMatteis* DATE 12/4/52
REGISTERED LAND SURVEYOR