

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
Kalkaska Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____

2. Property Controlling in Section S 24 T 26N R 6W 13
 S 24 T 26N R 6W CNSE1/64

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on March 19, 2009 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

13 - None CNSE 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

13 - SE 1/16 Corner Sec. 24 -
 Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM procedure. In tag elder swamp, North 55'± to Bottom of Bank. South 55'± to N'ly edge of Stream. East 82'± to W'ly edge of stream.

CNSE 1/64 corner in Sec. 24 - being the SW Cor. of the N 1/2 of the NE 1/4 of the SE 1/4 of Sec. 24, T26N, R6W -
 Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar.
 S70°W 45.66' to set N & T in N. side 14" R. Maple
 N83°W 32.30' to set N & T in S. side 12" Spruce
 N25°W 31.26' to set N & T in W. side 14" R. Maple
 N31°E 60.51' to set N & T in N. side 10" Cedar
 Set Blue Carsonite Post with loc tag 1' SW

CNSE 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
 N3°W 63.72' to set N & T in W. side 11" R. Maple
 N23°W 94.88' to set N & T in W. side 17" S. Maple
 N64°W 69.52' to set N & T in S. side 6" Ironwood
 N64°E 87.66' to set N & T in NE side 10" & 13" Tw. S. Maple
 Set Blue Carsonite Post with loc. Tag 1' NW

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 11/23/2009