

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>26N</u> R <u>6W</u> S <u>24</u> T <u>26N</u> R <u>6W</u>	<u>14</u> <u>NS 1/64</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Feb. 26, 2009 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

14 - None

NS 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

14 - S 1/16 Corner common to Sec. 24, T26N, R6W and Sec. 19, T26N, R5W - Set 2" Alum. Cap on 5/8" x 4' long rebar in Cedar swamp per standard BLM procedure

NS 1/64 - Corner common to Sec. 24, T26N, R6W and Sec. 19, T26N, R5W - being the SE Corner of the N 1/2 of the NE 1/4 of the SE 1/4 of Sec. 24, T26N, R6W - Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM procedure. Corner on Top of Bank. South 50'± to bottom of bank and 122'± to Edge of Stream course West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

14 - Stamped 2" Alum. Cap on 5/8" x 4' long iron rebar
Set Blue Carsonite Post with Loc. Tag 1' SE
N48°W 45.16' to set N & T in SW side 6" Cedar
N43°E 13.95' to set N & T in NW side 10" Cedar
S52°E 24.85' to set N & T in SW side 5" Cedar
S55°W 31.05' to set N & T in SE side 3" R. Maple

NS 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
Set Blue Carsonite Post with Loc. Tag 1' NE
S81°W 42.28' to set N & T in S. side 16" R. Maple
N26°W 50.65' to set N & T in E. side 9" Oak
N43°E 50.67' to set N & T in NW side 15" R. Maple
N73°E 42.80' to set N & T in N. side 16" R. Maple

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 11/23/2009