

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on OCTOBER 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
A-2: West 1/4 Cor. Sec. 6, T26N-R7W, Orange Township
 06-13-1902, Co. Surveyor, used corner, no accessories
 05-11-1987, DNR, LCR, set DNR mon & Cedar post, w/accessories, Lib. 2, Pg. 347
 07-06-1992, Grand Traverse Surveying Co., Cert. Survey, fd. DNR mon., w/accessories, Lib. 4, Pg. 77

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-2: West 1/4 Cor. Sec. 6, T26N-R7W, Orange Township
 Fd. DNR mon., w/Cedar post. Left in place. The Kalkaska Co. Peer group approved & accepted the above monument. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-2: West 1/4 Cor. Sec. 6, T26N-R7W, Orange Township
 Fd. DNR mon., w/Cedar post. Left in place.
 North, Kalkaska Co. mon. (E 1/4 cor. Sec. 1, T26N-R8W) 21.95' (Standard corner)
 Set nail & tag N42E, 14" W. Pine, 58.62'
 Fd. Spike S34E, 12" Maple, 30.08'
 Set nail & tag S88W, 14" Tw. Hemlock, 30.75'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene FARRIER
 Date 1-29-98



Signed by Eugene FARRIER
 Surveyor's Michigan License No. 24594

Date 2-3-98



3004808
 Page: 1 of 1
 02/04/98 11:22A
 LB: 5 PG: 217