

SURVEY & REMONUMENTATION

FEB 13 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

KALKASKA Located In: _____ Corner Code # _____
(County)
1997 REMONUMENTATION
1. Public Land Survey T 26N R 7W A-3
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		13		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 10, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-3: Sec. Cor. Common to Sec. 6 & 7, T26N-R7W, Orange Township
1849, GLO resurvey, set Hemlock post, 12" Hemlock, S44E, 26, 15" Hemlock N32E, 49
05-13-1987, C.F. Roser #12028 DNR drawing & LCR, fd. 3/4" pipe added 5/8" x 18" rerod & cap w/accessories, Lib. 2, Pg. 345
01-05-1973, J. H. Granger #16041, LCR, fd. iron pipe, w/accessories, Lib. 1, Pg. 159
05-03-1996, Farrier Surveying, survey, fd. 5/8" iron & cap 12028, w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-3: Sec. Cor. Common to Sec. 6 & 7, T26N-R7W, Orange Township
Fd. 5/8" iron w/cap 12028. Removed cap, left iron in place, placed brass cap on iron, 51' S. Of C.L. Gregg Rd. to East. No GLO witnesses were fd. The Kalkaska Co. Peer group approved & accepted the above monument as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-3: Sec. Cor. Common to Sec. 6 & 7, T26N-R7W, Orange Township
Fd. 5/8" iron w/cap 12028. Removed cap, left iron in place, placed brass cap on iron, 51' S. Of C.L. Gregg Rd. to East.
Fd. N03E DNR mon. 93.06'
Fd. nail N67E 4" W. Pine 11.23'
Fd. nail S20E 7" Cedar 48.47'
Fd. nail N65W 12" W. Pine 41.08'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-29-98

Signed by Eugene Farrier Date 2-3-98
Surveyor's Michigan License No. 24594