

# SURVEY & REMONUMENTATION

FEB 13 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in

KALKASKA Located In: Corner Code #  
(County)  
1997 REMONUMENTATION  
1. Public Land Survey T 26N R 7W A-7  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 28, 1997  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
A-7: Sec. Cor. common to Sec. 18 & 19, T26N-R7W, Orange Township  
1849, GLO resurvey, set Beech post, 18" Beech N55E, 47, 24" Sugar, S20E, 9  
07-07-1982, Farrier Surveying, LCR, fd. 1/2" iron rod & cap "(?)", w/accessories, Lib. 2, Pg. 401 (8.35' North of set corner)  
09-19-1984, Farrier Surveying, Cert. Survey, set 1/2" iron & cap, S.P.M., w/accessories  
04-29-1993, Grand Traverse Surveying Co., Cert. Survey, fd. 1/2" iron rod, w/accessories, Lib. 4, Pg. 281

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-7: Sec. Cor. common to Sec. 18 & 19, T26N-R7W, Orange Township  
Fd 1/2" x 18" rebar in C.L. Puffer Rd. & Boardman Rd. Extended East (0.25' West of Standard line). Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box. No GLO witnesses were fd. The Kalkaska Co. Peer group approved & accepted the monument as a careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-7: Sec. Cor. common to Sec. 18 & 19, T26N-R7W, Orange Township  
Fd 1/2" x 18" rebar in C.L. Puffer Rd. & Boardman Rd. Extended East. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box.  
North, Kalkaska Co. mon. 61.22' (M-7, T26N-R8W) (Standard Corner)  
North, 1/2" iron, 8.35'  
S35E, stop sign post, 43.80'  
Fd. nail, S87W P. Pole, 103.74'

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman Eugene Farrier  
Date 1-29-98

Signed by Eugene Farrier Date 2-3-98  
Surveyor's Michigan License No. 24594