

# SURVEY & REMONUMENTATION

FEB 13 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>KALKASKA</u>	Located In:	Corner Code #	
(County)			
1997 REMONUMENTATION			
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>A-8</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

A-8: West 1/4 corner Sec. 19, T26N-R7W, Orange Township  
 07-07-1982, Farrier Surveying, LCR, fd. 1/2" rod, w/accessories, Lib 2, Pg. 401  
 07-09-1982, Farrier Surveying, Cert. Survey, fd. 1/2" rod, w/accessories, Lib. 2, Pg. 813  
 07-08-1991, Farrier Surveying, Cert. Survey, used cor. No accessories


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-8: West 1/4 corner Sec. 19, T26N-R7W, Orange Township  
 Fd. 1/2" rebar, 1' West of CL Puffer Rd and 0.57' East of Standard line. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box. The Kalkaska Co. Peer group approved & accepted the above monument. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-8: West 1/4 corner Sec. 19, T26N-R7W, Orange Township  
 Fd. 1/2" rebar, 1' West of CL Puffer Rd. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box.  
 Fd. Nail S88W, P. Pole, 30.55'  
 Fd. North, Kalkaska Co. mon. (E 1/4 cor. Sec. 24, T26N-R8W) 89.91' (Standard corner)  
 S38E, fence post, 42.23'  
 N06E, 3/8" iron 41.82'

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman Eugene Farrier  
 Date 1-29-98



Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 2-3-98



**3004814**  
 Page: 1 of 1  
 02/04/98 11:22A  
 LB: 5 PG: 218