

**SURVEY & REMONUMENTATION**

**FEB 13 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>A-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on OCTOBER 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
A-12: West 1/4 Cor. Sec. 31, T26N-R7W, Orange Township  
05-15-1981, Farrier Survey, Cert. Survey, fd. 1" pipe, w/accessories, Lib. 2, Pg. 292  
05-15-1981, Farrier Survey, LCR, fd. 1" pipe, w/accessories, Lib. 2, Pg. 292

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-12: West 1/4 Cor. Sec. 31, T26N-R7W, Orange Township  
Fd. 1" iron pipe, 1' West C.L. Puffer Rd. & 8' South of C.L. Luce Rd. to East and 3.98' East of Stand line. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box. The Kalkaska Co. Peer group approved & accepted the above monument. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman Eugene Farrier  
Date 1-29-98



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-12: West 1/4 Cor. Sec. 31, T26N-R7W, Orange Township  
Fd. 1" iron pipe, 1' West C.L. Puffer Rd. & 8' South of C.L. Luce Rd. to East. Pulled and replaced with 5/8" x 18" rebar, w/brass cap in mon. box.  
North, Kalkaska Co. mon. (E. 1/4 cor. Sec. 36, T26N-R8W), 238.77' (Standard corner)  
N50E, stop sign post, 49.73'  
Set nail & tag S55E, 8" R. Pine, 85.15'  
Fd. Nail N68W, 7" Tw. Cherry, 53.35'

Signed by Eugene Farrier  
Surveyor's Michigan License No. 24594

Date 2-3-98



3004818  
Page: 1 of 1  
02/04/98 11:22A  
LB: 5 PG: 222