

**SURVEY &
REMONUMENTATION**

FEB 13 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>B-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
B-1: N 1/4 Corner Sec. 6, T26N-R7W, Orange Township
 1849, GLO resurvey, set Post, 12" Beech, N54E 19, 8" Beech, S31W 6
 05-12-1987 C. Roser #12028, LCR, drove 5/8" x 18" rerod w/cap, w/accessories, Lib. 2, Pg. 348
 07-06-1992, Grand Traverse Survey Co., Cert. Survey, fd. Iron no accessories, Lib. 4, Pg. 78

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-1: N 1/4 Corner Sec. 6, T26N-R7W, Orange Township
 Fd. 5/8" rerod & cap DNR, could not read #, 0.5' South of C/L Thomas Rd. (E-W). Pulled & replaced with 5/8" x 18" rerod w/brass cap in mon. box. No GLO witnesses were fd. The Kalkaska peer group approved & accepted the above monument. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-1: N 1/4 Corner Sec. 6, T26N-R7W, Orange Township
 Fd. 5/8" rerod & cap DNR, could not read #, 0.5' South of C/L Thomas Rd. (E-W). Pulled & replaced with 5/8" x 18" rerod w/brass cap in mon. box.
 East, Kalkaska Co. mon. S 1/4, Sec. 31, T27N-R7W 75.46' (Standard corner)
 Fd. South, iron & cap #31611 33.00'
 Fd. Nail N28W, fence post 51.88'
 Set nail & tag S36W, 10" R. Pine 48.42'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98



Signed by Eugene Farrier Date 2-3-98
 Surveyor's Michigan License No. 24594