

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #	
(County)			
1997 REMONUMENTATION			
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>B-5</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on AUGUST 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
B-5: 1/4 common Sec. 7 & 18, T26N-R7W, Orange Township
 1850, GLO resurvey, set Beech cor., 24" Beech S75E, 33, 24" Cedar N50W, 32
 01-29-1988, Farrier Surveying, LCR, fd. 3/4" bolt raised w/1/2" iron & cap 24594 w/accessories, Lib. 2, Pg. 381
 04-29-1993, Grand Traverse Surveying Co., Cert. Survey, fd. 1/2" iron, w/accessories, Lib 4, Pg. 281

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-5: 1/4 common Sec. 7 & 18, T26N-R7W, Orange Township
 Fd. 1/2" x 18" rebar w/cap 24594 & 3/4" x 12" bolt spike 2' South of C.L. Bass Lake Rd. Pulled both & set 5/8" x 18" rebar w/brass cap. No GLO witnesses were fd. The Kalkaska Co. Peer group approved & accepted the above monument as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-5: 1/4 common Sec. 7 & 18, T26N-R7W, Orange Township
 Fd. 1/2" x 18" rebar w/cap 24594 & 3/4" x 12" bolt spike 2' South of C.L. Bass Lake Rd. Pulled both & set 5/8" x 18" rebar w/brass cap.
 Fd. Nail N05W 10" Cedar, 45.75'
 Fd. Nail N33E 16" Maple 46.63'
 Set nail & tag S58E P. Pole, 68.40'
 Fd. Nail N33W 8" Cedar, 41.03'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-3-98 Surveyor's



3004822
 Page: 1 of 1
 02/04/98 11:22A
 LB: 5 PG: 226