

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

97 JAN 31 PM 3:19

Jean Hall
REG. DEEDS

For corners in

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code #1
1996 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>C-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on July 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2								
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-06: Cor. common to Sec. 17 & 18, T26N-R7W, Orange Township
 1849, GLO resurvey, set Beech cor. post, 9" Sugar S86W 27, 5" Beech N46E 10.
 May 20, 1880, G.A. Leinpert, Co. Surveyor, used cor. no accessories.
 May 05, 1903, W.S. Merrill, Co. Surveyor, fd. Cedar Stake, 30" Maple S88W 62.
 11-29-1973, LCRC Liber 1 Pg. 286.
 12-17-1973, J.L. Fletcher, set iron, Liber 1 pgs. 524-530 of Survey.
 03-22-1974, J.L. Wilcox, fd. 1/2" iron, Liber 1 pg. 499 of Survey.
 04-10-1978, J.L. Fletcher, fd. 1/2" iron, Liber 2 pg. 201 of Survey.
 07-30-1986, Farrier Surveying, fd. 3/8" iron and used. Survey #7986
 11-10-1987, E.D. Farrier, Survey #14289, fd. iron w/ accessories.
 06-03-1988, LCRC Liber 2 pg. 357.
 08-17-1989, E.D. Farrier, Survey #14089 & 14189, fd. iron w/ accessories.
 04-29-1993, Grand Traverse Surveying, used cor., Liber 4 pg. 281 & 156 of Survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


C-06: Cor. common to Sec. 17 & 18, T26N-R7W, Orange Township
 Found 5/8" x 18" re-rod w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap & mon box, cor falls 0.5' East of centerline of Ludlow rd. No good occupation to East or West, also no G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-06: Cor. common to Sec. 17 & 18, T26N-R7W, Orange Township
 Found 5/8" x 18" re-rod w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap & mon box, cor falls 0.5' East of centerline of Ludlow rd. No good occupation to East or West.
 East fd. 1/2" iron, 33.34'
 Set nail & tag S30E, 13" Elm, 53.40'
 Set nail & tag S55W, 5" Elm, 39.17'
 West fd. Iron & cap #24617

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *[Signature]*

Signed by *Eugene Farrier* Date 1-30
 Surveyor's Michigan License No. 24594



BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1971
REVISED JAN., 198