

# SURVEY & REMONUMENTATION

FEB 13 1998

## SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
**C-11: Cor. common Sec. 29, 30, 31 & 32, T26N-R7W, Orange Township**  
 1849, GLO resurvey, set beech post, 11" Hemlock N30E, 44, 16" Sugar S65W, 28  
 11-22-1900, W.S Merrill, Co. Surveyor, used cor. no accessories  
 04-02-1910, County Surveyor, used cor., no accessories, Kalkaska Co. Survey records, fd old corner stone  
 10-1973, J.L. Wilcox & Assoc., LCR, restore cor. from old fence ties to school and road ROW's in C.L. North & E-W, w/accessories, Lib. 1, Pg. 300  
 11-05-1973, Wilcox, Erickson & Assoc. Inc., Cert. Survey, fd. 1/2" iron & cap, w/accessories, Lib. 1, Pg. 495  
 02-17-1995, Farrier Surveying, Cert. Survey, fd. iron & cap w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**C-11: Cor. common Sec. 29, 30, 31 & 32, T26N-R7W, Orange Township**  
 Fd. 1/2" x 24" rebar w/cap, cannot read number. 1' North C.L. Montgomery Rd., and C.L. Ryckman Rd. To North. Pulled and replaced with 5/8" x 18" rebar w/brass cap in mon. box No GLO witnesses were fd. The Kalkaska Co. Peer group approved the above monument as careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**C-11: Cor. common Sec. 29, 30, 31 & 32, T26N-R7W, Orange Township**  
 Fd. 1/2" x 24" rebar w/cap, cannot read number. 1' North C.L. Montgomery Rd., and C.L. Ryckman Rd. To North. Pulled and replaced with 5/8" x 18" rebar w/brass cap in mon. box.  
 Set nail & tag N75E 30" Maple 71.34'  
 Set nail & tag S60E 42" Tw. Maple 69.48'  
 Set nail & tag S23W 10" R. Pine 59.62'  
 Set nail & tag N68W fence post tele riser, 101.81'

Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County  
 Chairman Eugene Farrier  
 Date 1-29-98

Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 2-3-98



3004830  
 Page: 1 of 1  
 02/04/98 11:22A