

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #	
(County)			
1997 REMONUMENTATION			
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>D-9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____


5. Private Claims _____

I, EUGENE FARRIER, in a field survey on OCTOBER 24, 1997
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9				●									
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
D-9: 1/4 Cor. Common to Sec. 20 & 29, T26N-R7W Orange Twp.
 1849, GLO, resurvey, set Beech post, 6" Sugar N11E, 20, 6" Beech S32W, 15
 09-15-1902, W.S. Merrill, County Surveyor, , Iron stake, no accessories
 04-02-1910, County Surveyor, Iron pipe, no accessories
 08-26-1976, Granger Eng. Inc., Cert. Survey, Fd. 2 1/2" pipe, w/accessories, Lib. 1, Pg. 928
 03-29-1990, Farrier Surveying, Cert. Survey, fd. 1 1/4" iron pipe, w/accessories
 03-29-1990, Farrier Surveying, LCR, fd. 1 1/4" iron pipe, w/accessories, Lib. 2, Pg. 402



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-9: 1/4 Cor. Common to Sec. 20 & 29, T26N-R7W Orange Twp.
 Fd. 1/2" x 18" rebar, pulled, fd. 1 1/2" iron pipe. Pulled and replaced with 5/8" x 18" rebar, w/brass cap 1.5' South of CL Hall Rd. No GLO witnesses were fd. The Kalkaska Co. Peer group approved the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-9: 1/4 Cor. Common to Sec. 20 & 29, T26N-R7W Orange Twp.
 Fd. 1/2" x 18" rebar, pulled, fd. 1 1/2" iron pipe. Pulled and replaced with 5/8" x 18" rebar, w/brass cap 1.5' South of CL Hall Rd.
 Set nail and tag S05E, 36" Maple, 46.47'
 Set nail and tag S62W, 10" Maple (clump), 41.17'
 Fd. Nail N52W, 15" Maple, 60.89'
 Set nail and tag N70E, 10" Ash, 31.41'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-3-98 Surveyor's



3004833
 Page: 1 of 1
 02/04/98 11:22A