

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T. 26N R. 7W	D-13
	T. 25N R. 7W	D-1
	T. ___ R. ___	_____
	T. ___ R. ___	_____
2. Property Controlling in Section	S. ___ T. ___ R. ___	_____
	S. ___ T. ___ R. ___	_____
3. Miscellaneous	S. ___ T. ___ R. ___	_____
Property in Sec.	S. ___ T. ___ R. ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13: 1/4 Cor. Common to Sec. 32, T26N-R7W Orange Twp., & Sec. 5, T25N-R7W, Garfield Twp. 1849, GLO, resurvey, set Beech post, 6" Beech N13W, 35, 18" Sugar N72E, 4 11-22-1900, W.S. Merrill, County Surveyor, fd. Old stake & one bearing tree, no accessories 07-13-1984, N.B. DeYoung #20705, Cert. Survey, fd. 1 1/2" pipe, w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-13: 1/4 Cor. Common to Sec. 32, T26N-R7W Orange Twp., & Sec. 5, T25N-R7W, Garfield Twp. Fd. 1 1/2" iron pipe at fence cor. North & East. Pulled and replaced with 5/8" x 18" rebar, w/aluminum cap. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13: 1/4 Cor. Common to Sec. 32, T26N-R7W Orange Twp., & Sec. 5, T25N-R7W, Garfield Twp. Fd. 1 1/2" iron pipe at fence cor. North & East. Pulled and replaced with 5/8" x 18" rebar, w/aluminum cap. Set nail & tag N37E, 7" R. Pine, 53.35' Set nail & tag S75E, 10" Cherry, 16.40' Set nail & tag South, 3" Cherry, 48.10' Set nail & tag S36W, 3" Cherry, 49.85'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 1-29-98



Signed by Eugene Farrier
Michigan License No. 24594

Date 2-3-98 Surveyor's



3004835
Page: 1 of 1
02/04/98 11:22A
REMON Q 00 1B: 5 PG: 239