

**SURVEY &
REMONUMENTATION**

JAN 17 1996

COMMISSION

For corners in

KALKASKA

(County)

1995 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

95 DEC 27 AM 9:54

Jan Hall
REG. DEEDS

Register of Deeds Stamp & File Number

	Located In:	Corner Code #1
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	E-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman *Eugene Farrier*
 Date 12-19-95

I, EUGENE FARRIER, in a field survey on Oct. 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6			5	4			3				2
3												
4	7			8	9			10				11
5												
6	18			17	16			15				14
7												
8	19			20	21			22				23
9												
10	30			29	28			27				26
11												
12	31			32	33			34				35
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-1: Cor. common to Sec. 4 & 5, T26N-R7W, Orange
 1849 GLO re-survey: set post, Sugar 16", S19E, 35; Beech 8", S54W, 94.
 11-8-1897, E.P.Beebe, Surv., Hwy. Surv. btwn Sec. 4 & 5, stake & stone.
 M.S.H.D. Surv. for M-66
 9-22-1975, H.L.Fluharty, CERT OF SRV, fd. 1 1/4" hub in Mon. box, L.1 PG.759.
 11-5-1975, LCRC(H.L.Fluharty), E-1, fd. 1 1/4" hub in Mon. box, L.1 PG.366.
 4-22-1977, J.L.Fletcher, CERT OF SRV, fd. 1" bolt in Mon. box, L.1 PG.992.
 6-14-1977, LCRC(J.L.Fletcher), E-1, fd. 1" bolt in Mon. box, L.2 PG.13.
 11-6-1985, E.D.Farrier, CERT OF SURVEY, L.3 PG.27-28.
 4-16-1986, E.D.Farrier, CERT OF SURVEY, fd. 1' bolt in Mon. box.
 1-15-1990, T.E.Brand, CERT OF SURVEY, fd. 1" bolt in Mon. box.
 3-5-1990, E.D.Farrier, CERT OF SURVEY, fd. 1" bolt in Mon. box.
 6-4-1991, E.D.Farrier, CERT OF SURVEY, fd. 1" bolt in Mon. box, L.4 PG.55.
 5-25-1993, E.D.Farrier, CERT OF SURV, fd. 1" bolt in Mon. box, L.4 PG.161.
 6-6-1994, E.D.Farrier, CERT OF SURVEY, fd. 1" bolt in Mon. box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1: Cor. common to Sec. 4 & 5, T26N-R7W, Orange
 Fd 1" iron bolt 44.7' W c/1 M-66 in Mon. box. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: Cor. common to Sec. 4 & 5, T26N-R7W, Orange
 Fd 1" iron bolt. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Thomas Rd. Surface.
 Set nail & tag N74W, P.P., 226.96'
 Set nail & tag N67W, 8" Twin Elm, 90.83'
 East, Cor. common to Sec. 32 & 33, T27N-R7W, Kal.Co.Mon, 54.96'
 Set nail & tag S40E, 8" R. Pine, 141.65'

Signed by *Eugene Farrier* Date 12-22-95
 Surveyor's Michigan License No. 24594

