

**SURVEY & MONUMENTATION**

JAN 17 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN  
 RECEIVED  
 95 DEC 27 AM 9:54

*Jan Hall*  
 CLERK OF DEEDS

For corners in

KALKASKA (County)	Located In:	Corner Code #1
1995 REMONUMENTATION		
1. Public Land Survey	T 26N R 7W	E-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Ratified by Peer Group  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman *[Signature]*  
 Date 12-19-95

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, EUGENE FARRIER, in a field survey on Nov. 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-2: 1/4 Cor. common to Sec. 4 & 5, T26N-R7W, Orange 1849 GLO re-survey: set Bech post, Sqr 13", N45E, 38; Bech 20", WST, 24. 8-26-1895, E.B.Dennis, Co.Srv,stk, Bech 16"N48W,36.5,Bech 65.5W,60,Maple stp 24"S40.5E,63. 1937, MDOT, fd. 1/8"x4"x18" tapered iron, w/accessories. 9-22-1975, H.L.Fluhart, CERT OF SURVEY, L.1 PG.759. 4-22-1977, J.L.Fletcher, CERT OF SRV, fd.pknail-Reset w/1/2"rod, L.1 P.992. 6-14-1977, LCRC(J.L.Fletcher), E-2, fd.pknail-Reset w/1/2" rod, L.2 PG.13. 5-24-1979, J.L.Fletcher, CERT OF SURV, fd. 1/2" iron rod, L.2 PG.347. 11-6-1985, E.D.Farrier, CERT OF SURV, fd. 1/2" iron rod, L.3 PG.27-28. 1-15-1990, T.E.Brand, CERT OF SURVEY, fd. 1/2" iron rod. 3-5-1990, E.D.Farrier, CERT OF SURVEY, fd. 1/2" iron rod. 6-4-1991, E.D.Farrier, CERT OF SURV, fd. 1/2" iron rod, L.4 PG.55. 6-6-1994, E.D.Farrier, CERT OF SURVEY, fd. pknail-Reset w/1/2" rod. 10-10-1994, E.D.Farrier, CERT OF SURV, fd. 1/2" iron rod in Mon.box.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-2: 1/4 Cor. common to Sec. 4 & 5, T26N-R7W, Orange Fd 1/2" iron rod in Mon.box, 1' East of c/l M-66. Pulled & replaced with 5/8" x 18" R.B. w/brass cap in old Mon.box. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-2: 1/4 Cor. common to Sec. 4 & 5, T26N-R7W, Orange Fd 1/2" iron rod. Pulled & replaced with 5/8" x 18" R.B. w/brass cap in old Mon.box. Set pknail East, East shoulder M-66, 12.00' Fd. RR spike S60E, East edge North bound lane M-66, 12.00' Set nail & tag N70W, 6" J.Pine, 42.25' Fd. RR spike N34W, West edge North bound lane M-66, 20.00'

Signed by *[Signature]*  
 Surveyor's Michigan License No. 24594

Date 12-22-95



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS