

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN RECEIVED

97 JAN 31 PM 3:19

For corners in

KALKASKA
(County)

Located In:

Corner Code #

1996 REMONUMENTATION

- | | | | | | |
|------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 26N | R | 7W | E-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jean Hall
REG DE 7711

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on Nov. 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-06: Cor. common to Sec. 16 & 17, T26N-R7W, Orange Township
1849, GLO resurvey, set Beech post, 6" Beech East 28, 6" Sugar S40W 14.
Sep 1885, E.Mosher, Co. Surveyor, used cor. no accessories.
Aug 1887, E.Mosher, Co. Surveyor, used cor. no accessories.
May 5, 1903, W.S.Merrill, Co. Surveyor, used cor. no accessories.
Sep 17, 1914, W.S.Merrill, Co. Surveyor, used cor. no accessories.
12-22-1967, W.B.Batzer, used corner no accessories.
11-29-1973, LCRC Liber 1 pg. 288.
12-28-1978, J.L.Fletcher, fd 1/2" iron rod in mon. box. Liber 2 pg. 331 of Survey.
12-28-1978, LCRC Liber 2 pg. 172.
07-30-1986, Farrier Surveying, fd 1/2" iron rod in mon. box no accessories.
08-01-1986, E.D.Farrier, Survey #7986, used corner, no accessories.
08-11-1988, E.D.Farrier, Survey #9588, used corner, no accessories.
08-31-1989, J.G.Knapp, fd iron. Liber 3 pg. 335 of Survey.
02-17-1992, E.D.Farrier, Survey #3192, fd mon. box w/ accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-06: Cor. common to Sec. 16 & 17, T26N-R7W, Orange Township
Found 1/2" x 18" re-rod in Mon Box w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 5.2' West of centerline of M-66, online w/ split rail fence to East. No GLO witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-06: Cor. common to Sec. 16 & 17, T26N-R7W, Orange Township
Found 1/2" x 18" re-rod in Mon Box w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 5.2' West of centerline of M-66, online w/ split rail fence to East.
Set nail & tag East Fence Post, 44.18'
Set nail & tag S57E Power Pole, 102.35'
Set nail & tag N62W 13" R.Pine, 57.60'
Set nail & tag N35W 10" R.Pine, 73.30'

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 1-21-97

Signed by *Eugene Farrier* Date 1-27-97

Surveyor's Michigan License No. 24594

