

SURVEY & REMONUMENTATION

FEB 13 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA	Located In:	Corner Code #	
(County)			
1997 REMONUMENTATION			
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>E-8</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-8: Cor. Common to Sec. 20, & 21, T26N-R7W Orange Twp.
 1849, GLO, resurvey, set Sugar post, 10" sugar N29W, 15, 14" Sugar N76E, 16
 09-11-1902, W.S. Merrill Co. Surveyor, Est. Cor. SPM, set Cedar stake, w/accessory
 05-23-1979, Granger Engineering, Cert. Survey, set 1/2" rod & cap, w/accessories, Lib. 2, Pg. 366
 10-30-1981, Farrier Surveying, Cert. Survey (witnessed in Lib. 2, Pg. 366)
 12-15-1993, Farrier Surveying, Cert. Survey fd. 1/2" rerod, w/accessories, Lib. 4, Pg. 225
 07-26-1996, Farrier Surveying, Cert. Survey fd. 1/2" rerod, w/accessories



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-8: Cor. Common to Sec. 20, & 21, T26N-R7W Orange Twp.
 Fd. 1/2" rebar in mon. box, 1.3' West of CL Hwy. M-66. Pulled and replaced with 5/8" x 18" rebar, w/brass cap. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as a careful and faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-8: Cor. Common to Sec. 20, & 21, T26N-R7W Orange Twp.
 Fd. 1/2" rebar in mon. box, 1/3' West of CL Hwy. M-66. Pulled and replaced with 5/8" x 18" rebar, w/brass cap
 S85°W, top of conc. ROW marker 60.35'
 Set nail & tag N45°E 3" R. Pine 54.47'
 Set nail & tag N76°E 5" R. Pine 38.04'
 South Bolt Spk. (Road P.T.) 7.28'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 1-29-98

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-3-98 Surveyor's



3004836
 Page: 1 of 1
 02/04/98 11:22A