

**SURVEY &  
REMONUMENTATION**

**FEB 13 1998**

**SECTION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	<u>T 26N R 7W</u>	<u>E-9</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No.     , Recorded Plat     

5. Private Claims     

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on NOVEMBER 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
E-9: Cor. Common to Sec. 20, 21, 28, & 29, T26N-R7W Orange Twp.  
 1849, GLO, resurvey, corner in lake  
 05-18-1880, Co. Surveyor, Highway Survey, used cor., w/accessories  
 09-15-1902, W.S. Merrill Co. Surveyor, corner in lake, no accessories  
 08-23-1975, N.F. Parker #16939, Cert. Survey, used cor., no accessories, Lib 2, Pg. 457  
 08-26-1976, Granger Engineering, Cert. Survey, fd. 2" iron pipe, w/accessories Lib. 1, Pg. 928  
 10-14-1976, DNR, LCR, fd. 1 1/2" pipe w/accessories, Lib. 2, Pg. 68  
 05-23-1979, Granger Engineering, Cert. Survey, fd. 2" iron w/accessories Lib. 2, Pgs. 348 & 366  
 12-15-1993, Farrier Surveying, Cert. Survey, fd. 1 1/2" iron w/accessories Lib. 4, Pg. 225  
 07-02-1996, Farrier Surveying, Cert. Survey, fd. 1 1/2" iron w/accessories



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
E-9: Cor. Common to Sec. 20, 21, 28, & 29, T26N-R7W Orange Twp.  
 Fd. 1 1/2" iron pipe w/DNR post (lying down) in N. Edge of lake set 5/8" x 36" rebar, w/aluminum cap inside pipe. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-9: Cor. Common to Sec. 20, 21, 28, & 29, T26N-R7W Orange Twp.  
 Fd. 1 1/2" iron pipe w/DNR post (lying down) in N. Edge of lake set 5/8" x 36" rebar, w/aluminum cap inside pipe.  
 Set nail & tag N45°W 5" W. Pine 59.77'  
 Set nail & tag N30°W 5" Maple 59.80'  
 Set nail & tag N17°W 10" W. Pine 59.50'  
 Set nail & tag North 12" W. Pine 73.50'  
 South North edge of lake ± 15'

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman Eugene Farrier  
 Date 1-29-98

Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 2-3-98



**3004837**  
 Page: 1 of 1  
 02/04/98 11:22A