

**SURVEY &
REMONUMENTATION**

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

95 DEC 27 AM 9:54

Joan Hall
REG. DEEDS

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #:
1995 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>F-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on Oct. 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3: Cor. common to Sec. 4 & 9, T26N-R7W, Orange
1850 GLO re-survey: Set Bech post, Sgr 12", N06E, 12; Bech 6", S15E, 24
6-6-1888, E.Mosher, Co.Surv, Hwy.Surv, on S. line, used crnr.
1937 MDOT, fd lg. tapered stone on S fence line and cl of Rds N, E, & W.,
Raised w/1 3/4" axle shaft w/access.
11-5-1975, LCRC(H.L.Fluhart), F-3, fd. 1 3/4" iron hub, L.1 PG.366.
11-17-1978, J.L.Fletcher, CERT OF SURV, fd. 2" iron pipe, L.2 PG.278.
1-3-1983, E.D.Farrier, CERT OF SURV, fd. 2" iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3: Cor. common to Sec. 4 & 9, T26N-R7W, Orange
Fd 1 3/4" axle shaft, 5' East of c/l of Krumlauf Rd. & c/l of Pontius Rd.
to South. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below
Rd. Surface. No GLO wits were fd. The Kalkaska Co. peer group approved the
above monument and is accepted as the best available evidence of the
position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County


Chairman Eugene Farrier
Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3: Cor. common to Sec. 4 & 9, T26N-R7W, Orange
Fd 1 3/4" axle shaft. Pulled & replaced with 5/8" x 18" R.B. w/brass cap
0.3' below Rd. Surface.
Set nail & tag N55E, 6" R. Pine, 65.31'
Set nail & tag N67E, 4" R. Pine, 87.27'
Set nail & tag S65W, P.P., 49.14'
Set nail & tag N40W, P.P., 54.03'
Fd. nail, S12E, cut off T.P., 32.20'

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-95



FORM 4221

MICHIGAN STATE BOARD OF SURVEYORS
REVISED JAN., 1995