

**SURVEY & REMONUMENTATION**

MAR 21 1997

KALKASKA COUNTY, MICHIGAN RECEIVED

LAND CORNER RECORDATION CERTIFICATE 97 JAN 31 PM 3:19

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code <u>F-7</u>
1996 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Joan Hall*  
REG. DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on Oct. 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- F-07: Cor. common to Sec. 16 & 21, T26N-R7W, Orange Township 1849, GLO resurvey, Set Beech post, 12" Sugar N29E 12, 7" Sugar S42W 16 Sep 1885, E.Mosher, Co. Surveyor, used cor. no accessories.
- Aug 1887, E.Mosher, Co. Surveyor, used cor. no accessories.
- Sep 17, 1914, W.S.Merrill, Co.Surveyor, used cor. no accessories.
- 03-13-1965, Arthur G. Ericson, used corner no accessories.
- 11-08-1977, J.L.Fletcher, fd 1" iron pipe Liber 2 pg. 168 of Survey.
- 12-28-1978, LCRC Liber 2 pg. 172.
- 06-15-1982, E.D.Farrier, Survey #2482, fd 1/2" rod, w/ accessories.
- 04-22-1992, LCRC Liber 2 pg. 439.
- 04-22-1992, E.D.Farrier, Survey #21491, fd 1/2" iron, w/ accessories.
- 06-30-1995, R.J.Kral, Survey #11095, fd 1/2" iron, w/ accessories.
- 09-06-1995, R.J.Kral, Survey #13895, fd 1/2" iron, w/ accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-07: Cor. common to Sec. 16 & 21, T26N-R7W, Orange Township Found 1/2" x 18" iron and 1" x 18" iron pinch pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box in centerline of Spencer Road 1' East of fence to North & on fence to South. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-07: Cor. common to Sec. 16 & 21, T26N-R7W, Orange Township Found 1/2" x 18" iron and 1" x 18" iron pinch pipe w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box in centerline of Spencer Road 1' East of fence to North & on fence to South.  
Set nail & tag N23W 6" W. Pine, 65.73'.  
Set nail & tag North cor. fence post, 33.88' (old wit).  
Set nail & tag N55E Fence post, 55.31' (old wit).  
Set nail & tag 14" Chinese Elm, 32.60'.

Ratified by Peer Group  
P.A.345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 1-21-97



Signed by Eugene Farrier

Date 1-30-97

Surveyor's Michigan License No. 24594