

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN RECEIVED

97 JAN 31 PM 3:19

Jean Hall
 REG. CLERK

For corners in

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code #:
1996 REMONUMENTATION	T <u>26N</u> R <u>7W</u>	<u>G-6</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on July 8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 G-06: Cor. common to Sec. 15 & 16, T26N-R7W, Orange Township
 1849, GLO resurvey, set Beech cor. post, 13"Beech N06E 32, 11"Beech N58E 26.
 June 9, 1881, E. Mosher, Co. Surveyor, used cor. no accessories.
 Aug 1887, E. Mosher, Co. Surveyor, used cor. no accessories.
 Nov. 29, 1901, W.S. Merrill, Co. Surveyor, used cor. no accessories.
 Sept. 16&17, 1914, W.S. Merrill, Co. Surveyor, used cor. no accessories.
 4-22-1992, LCRC Liber 2 Pg. 439.
 4-22-1992, E.D. Farrier, Survey #21491, reestablished cor. 1/2" rod & cap at pro-rated computed location, shown on Grangers comp. sheet
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 G-06: Cor. common to Sec. 15 & 16, T26N-R7W, Orange Township
 Found 1/2" iron & cap w/ accessories. Pulled & Set 5/8" x 36" re-rod w/ Brass cap flush w/ ground, cor falls 2' North of & 7' West of centerline extended (Mitchell rd.). No good occupation left, also no G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-06: Cor. common to Sec. 15 & 16, T26N-R7W, Orange Township
 Found 1/2" iron & cap w/ accessories. Pulled & Set 5/8" x 36" re-rod w/ Brass cap flush w/ ground, cor falls 2' North of & 7' West of centerline extended (Mitchell rd.). No good occupation left.
 Set nail & tag N53W, 8" Maple, 14.27'
 Set nail & tag S73E, 24" Maple, 19.91'
 Set nail & tag S47E, 12" Beech, 26.65'
 South, Fd. iron & cap #24594, 33.00'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 9-21-97



Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 1-30-97