

**SURVEY & REMONUMENTATION**

MAR 21 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN  
RECEIVED  
97 JAN 31 PM 3:20

For corners in

KALKASKA  
(County)

Located in:

Corner Code ##

1996 REMONUMENTATION

1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Joan Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on Oct. 21, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
G-07: Cor. common to Sec. 15, 16, 21, & 22, T26N-R7W, Orange Township  
May 20, 1849, GLO resurvey, used corner no accessories.  
Jun 9, 1881, E. Mosher, Co. Surveyor, used cor. no accessories.  
Sep 1885, E. Mosher, Co. Surveyor, used cor. no accessories.  
Sep 17, 1914, W.S. Merrill, Co. Surveyor, used cor. no accessories.  
Jun 19, 1941, A.L. Dragoo, fd bronze plate in conc. post, no accessories.  
06-26-1974, J.L. Fletcher, fd broken mon. set 1/2 re-rod over mon. Liber 1 pg. 599.  
09-13-1977, LCRC Liber 2 pg. 173.  
11-08-1977, J.L. Fletcher, fd 1/2" re-rod. Liber 2 pg. 168 of Survey.  
06-15-1982, E.D. Farrier, Survey #2482, fd 1/2" rod, w/ accessories.  
04-22-1992, LCRC Liber 2 pg. 439.  
04-22-1992, E.D. Farrier, Survey #21491, fd 1/2" iron, w/ accessories.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
G-07: Cor. common to Sec. 15, 16, 21, & 22, T26N-R7W, Orange Township  
Found 1/2" x 12" R.B. left busted con. mon. in place w/ accessories.  
Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box 1.5' North of centerline of Spencer Road. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-07: Cor. common to Sec. 15, 16, 21, & 22, T26N-R7W, Orange Township  
Found 1/2"x12" R.B. left busted con. mon. box in place w/ accessories.  
Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box 1.5' North of centerline of Spencer Road.  
Set nail & tag N61W 13" W. Pine, 66.44'.  
Set nail & tag South Power Pole, 33.96'.  
Set nail & tag S40W 8" Maple, 56.45'.  
Set nail & tag S75W 12" W. Pine, 87.45'.



Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*  
Date 9-21-97

Signed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 1-30-97