

SURVEY &  
REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN  
RECEIVED

95 DEC 27 AM 9:55

*Joan Hall*  
REG. DEEDS

For corners in

KALKASKA

(County)

Located In:

Corner Code: #

Register of Deeds Stamp & File Number

|                                    |       |      |     |
|------------------------------------|-------|------|-----|
| 1995 REMONUMENTATION               |       |      |     |
| 1. Public Land Survey              | T 26N | R 7W | I-3 |
|                                    | T     | R    |     |
|                                    | T     | R    |     |
|                                    | T     | R    |     |
| 2. Property Controlling in Section | S     | T    | R   |
|                                    | S     | T    | R   |
| 3. Miscellaneous Property in Sec.  | S     | T    | R   |
|                                    | S     | T    | R   |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on Oct. 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-3: Cor. common to Sec. 2, 3, 10 & 11, T26N-R7W, Orange
- 1849 GLO re-survey: set Bech post, Sgr 20", N35E, 24; Bech 18", S28W, 31.
- 6-6-1876, D.E.McVee, Co.Surv., HwySurv, used crnr, no accessories.
- 11-22-1900, W.S.Merrill, Co.Surv., fd. old stake, no bearing trees.
- 9-8-1911, W.S.Merrill, Co.Surv., fd. stone corner.
- 8-1-1981, E.D.Farrier, COS, Set 1/2" rod w/cap by retracing Merrill survey.
- 4-28-1987, E.D.Farrier, CERT OF SURVEY, fd. 1/2" rod w/cap, L.3 PG.117.
- 4-11-1988, E.D.Farrier, CERT OF SURVEY, fd. 1/2" rod w/cap.
- 5-23-1991, N.L.Way, CERT OF SURVEY, fd. 1/2" iron rod.
- 6-3-1993, E.D.Farrier, CERT OF SURVEY, fd. 1/2" rod w/cap, L.1 PG.759.
- 8-30-1993, LCRC(E.D.Farrier), I-3, Set 1/2" rod w/cap.
- 5-27-1994, E.D.Farrier, CERT OF SURVEY, fd. 1/2" iron rod w/cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3: Cor. common to Sec. 2, 3, 10 & 11, T26N-R7W, Orange  
Fd 1/2" R.B. w/cap, 3.8' West c/l Saunders Rd. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-3: Cor. common to Sec. 2, 3, 10 & 11, T26N-R7W, Orange
- Fd 1/2" R.B. w/cap. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface.
- Set nail & tag N48E, P.P., 75.36'
- Set nail & tag S26W, 48" Maple, 90.63'
- Set nail & tag N58W, 30" Maple, 79.95'
- Set nail & tag S65E, P.P., 92.69'



Signed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-22-95

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1978  
REVISED MAY 14, 1988  
REVISED JAN. 1995