

**SURVEY &
DOCUMENTATION**

KALKASKA COUNTY, MICHIGAN
RECEIVED

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC 27 AM 9:55

For corners in
KALKASKA

COMMISSION

Located In:

Corner Code: I-4

Joan Hall
REC. OF DEEDS

1995 REMONUMENTATION				
1. Public Land Survey	T <u>26N</u> R <u>7W</u>			<u>I-4</u>
	T _____ R _____			_____
	T _____ R _____			_____
	T _____ R _____			_____
2. Property Controlling in Section	S _____ T _____ R _____			_____
	S _____ T _____ R _____			_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____			_____
	S _____ T _____ R _____			_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1. EUGENE FARRIER in a field survey on Oct. 23, 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4: 1/4 Cor. common to Sec. 10 & 11, T26N-R7W, Orange
1849 GLO re-survey: set Bech 1/4 post, Sgr 10", N68E, 13; Sgr 8", S40W, 21.
6-6-1876, D.E.McVee, Co.Surv., HwySurv, used crnr, no accessories.
11-10-1887, E.Mosher, Co.Surv., HwySurv, used crnr, no accessories.
11-22-1900, W.S.Merrill, Co.Surv., bearing tree of Govt.Resurvey.
9-8-1911, W.S.Merrill, Co.Srv, tree of Gov.rsrv, Mpl 10", N7E, 27.7'; Bech 14", S63W, 52.7'
8-27-1983, E.D.Farrier, CERT OF SURVEY, Set 1/2" iron w/cap, L.2 PG.792.
1-7-1987, LCRC(E.D.Farrier), I-4, Set 1/2" rod w/cap, L.2 PG.310.
5-23-1991, N.L.Way, CERT OF SURVEY, fd. 1/2" iron rod, L.4 PG.137.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4: 1/4 Cor. common to Sec. 10 & 11, T26N-R7W, Orange
Fd 1/2" R.B., 9.5' East c/l of Saunders Rd. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface w/Mon.box. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4: 1/4 Cor. common to Sec. 10 & 11, T26N-R7W, Orange
Fd 1/2" R.B. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface w/Mon.box.
Set nail & tag S78E, 6" Maple, 37.11'
Set nail & tag N70W, 7" Beech, 51.50'
Set nail & tag N40W, 10" Maple, 65.70'
Set nail & tag N25E, 4" Maple, 93.50'



Signed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-95