

**SURVEY &
REMONUMENTATION**

MAR 21 1997

KALKASKA COUNTY, MICHIGAN
RECEIVED

97 JAN 31 PM 3:20

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

John Hall
REG. DEEDS

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code -#
1996 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>I-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, EUGENE FARRIER, in a field survey on Nov. 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-06: Cor. common to Sec. 14 & 15, T26N-R7W, Orange Township
1849, GLO resurvey, set Sugar post. 14" Beech N72W, 15, 6" Beech S65E, 30.
Oct 1887, E. Mosher, Co. Surveyor, used cor. no accessories.
Jun 13, 1891, E. Mosher, Co. Surveyor, used cor. no accessories.
Sep 16, 1914, W.S. Merrill, Co. Surveyor, used cor. w/ accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-06: Cor. common to Sec. 14 & 15, T26N-R7W, Orange Township
Found 1/2" x 18" re-rod w/ cap #?. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in centerline of Saunders Road and on East-West fence. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*
Date 1-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-06: Cor. common to Sec. 14 & 15, T26N-R7W, Orange Township
Found 1/2" x 18" re-rod w/ cap #?. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in centerline of Saunders Road and on East-West fence.
Set nail & tag West Fence Post, 32.76'
Set nail & tag N48W 12" R. Pine, 58.78'
Set nail & tag East Fence Post, 29.28'
Set nail & tag S60W 10" R. Pine, 88.85'



Signed by *Eugene Farrier* Date 1-2
Surveyor's Michigan License No. 24594