

**SURVEY & REMONUMENTATION**

MAR 21 1997

KALKASKA COUNTY, MICHIGAN  
RECEIVED

**COMMISSION LAND CORNER RECORDATION CERTIFICATE** 97 JAN 31 PM 3:20  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code =#
1996 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Jean Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on Nov. 21, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-07: Cor. common to Sec. 14, 15, 22, & 23, T26N-R7W, Orange Township  
Jul 18, 1849, G.L.O. resurvey, set post. 10" Sugar S72W, 24, 10" Beech N87E, 18.  
1885, E. Mosher, Co. Surveyor, used cor. no accessories.  
Oct 1887, E. Mosher, Co. Surveyor, used cor. no accessories.  
Jun 13, 1891, E. Mosher, Co. Surveyor, used cor. no accessories.  
Sep 16, 1914, W.S. Merrill, Co. Surveyor, used cor. no accessories.  
07-17-1975, LCRC Liber 1 pg. 358.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-07: Cor. common to Sec. 14, 15, 22, & 23, T26N-R7W, Orange Township  
Found 5/8" x 18" re-rod w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in center line of intersection of Spencer & Saunders Rd. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**

Chairman *Eugene Farrier*  
Date 11-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-07: Cor. common to Sec. 14, 15, 22, & 23, T26N-R7W, Orange Township  
Found 5/8" x 18" re-rod w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in center line of intersection of Spencer & Saunders Rd.  
Set nail & tag N60W 20" Maple, 63.65'  
Set nail & tag S69E 22" Maple, 85.37'  
Set nail & tag South 30" Maple, 44.25'  
Set nail & tag S35W Cor Fence Post, 43.68'



Signed by *Eugene Farrier* Date 1-30-97  
Surveyor's Michigan License No. 24594