

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

95 DEC 27 AM 9:55

For corners in

KALKASKA

(County)

Located In:

Corner Code J-1

1995 REMONUMENTATION

- 1. Public Land Survey T 26N R 7W J-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Jean Hall
REG. DEPT.

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on Dec. 5, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1: N 1/4 Corner, Sec. 2, T26N-R7W, Orange
This corner not established by original government surveyors. Nothing on record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1: N 1/4 Corner, Sec. 2, T26N-R7W, Orange
Set 5/8" x 18" R.B. w/brass cap, 3' South of c/l of Anderson Rd. Set equal distance between closing corners and on line w/standard corners. This position not established by original government surveyors. The Kalkaska Co. peer group approved the above monument and is accepted as the best available evidence of the position of the corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1: N 1/4 Corner, Sec. 2, T26N-R7W, Orange
Set 5/8" x 18" R.B. w/brass cap.
Set nail & tag N55W, 14" Maple, 60.70'
Set nail & tag N72W, 16" Maple, 118.64'
Set nail & tag S78W, P.P., 154.69'
East, S 1/4 Cor., Sec. 35, T27N-R7W, Kal.Co.Mon, 54.29'



Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-95