

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN  
RECEIVED

95 DEC 27 AM 9:55

*Joan Hall*  
REG. DEPT.

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #1
1995 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	16	17	18	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, EUGENE FARRIER, in a field survey on Oct. 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-5: Cor. common to Sec. 11, 12, 14 & 15, T26N-R7W, Orange  
1850 GLO re-survey: set Bech post, Maple 16", N33E, 60; Birch 14", S60W, 26.  
7-15-1901, W.S. Merrill, Co. Surv., Set corner.  
9-27-1935, Kalkaska Cnty. Rd. Comm., Set iron Brake Road., w/access.  
12-4-1982, E.D. Farrier, CERT OF SURV, fd. 1" iron pipe.  
7-10-1986, E.D. Farrier, CERT OF SURV, fd. 1" iron pipe.  
8-30-1993, LCRC(E.D. Farrier), K-5, fd. 1" iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5: Cor. common to Sec. 11, 12, 14 & 15, T26N-R7W, Orange  
Fd 1" iron pipe, 1' West & 1' South of c/l int. of Cool Rd. & Golden Rd.  
Set 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface in Mon. box. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument and is accepted as the best available evidence of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5: Cor. common to Sec. 11, 12, 14 & 15, T26N-R7W, Orange  
Fd 1" iron pipe. Set 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface in Mon. box.  
Set nail & tag N40E, wood post, 79.70'  
Set nail & tag S47E, 26" Maple, 68.02'  
Set nail & tag N52W, 12" R. Pine, 77.48'  
Set nail & tag N22W, 12" R. Pine, 91.93'

Signed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-22-95

