

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

97 JAN 31 PM 3:20

For corners in

KALKASKA
(County)

Located in:

Corner Code #

1996 REMONUMENTATION

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>26N</u> R <u>7W</u> | <u>L-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Jean Hall
REG. DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EUGENE FARRIER, in a field survey on Nov. 21, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-07: Cor. common to Sec. 13 & 24, T26N-R7W, Orange Township
1849, GLO resurvey, set Ironwood post. 9" Sugar S45E 17, 13" Beech N32W 29.
04-27-1905, W.S. Merrill, fd corner, 12" Cherry S16W 42, 5" Maple N25W 24.
10-02-1974, W.E. Boss, used corner. Liber 2 pg. 480 of Survey.
12-03-1982, Farrier Surveying, fd 1/2" iron rod, opposite fence to North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-07: Cor. common to Sec. 13 & 24, T26N-R7W, Orange Township
Found 5/8" x 18" iron. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in centerline of Spencer Rd. No G.L.O. witnesses found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group

P.A. 345 - 1990 Kalkaska County

Chairman *Eugene Farrier*

Date 1-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-07: Cor. common to Sec. 13 & 24, T26N-R7W, Orange Township
Found 5/8" x 18" iron w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in Mon Box in centerline of Spencer Rd..
Set nail & tag N25W 18" Maple, 35.00'
Set nail & tag N77E 18" Maple, 78.34'
Set nail & tag S20W 30" Beech, 26.68'
Set nail & tag S62W 24" Tw. Maple, 42.39'



Signed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 1-30-97