

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

KALKASKA COUNTY, MICHIGAN RECEIVED

97 JAN 31 PM 2:26

CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in


KALKASKA
(County)

Located In:

Corner Code *##*

1996 REMONUMENTATION
Public Land Survey

T 26N R 6W
T 26N R 7W
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____



Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

EUGENE FARRIER, in a field survey on Oct. 1, 1996,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- A-06: Cor. comn to Sec. 18, T26N-R6W, Oliver Township, & Sec. 13, T26N-R7W, Orange Township
1849, GLO resurvey, set post. 15"Hemlock S48W 26, 6"Hemlock N62W 05.
June 23, 1881, E.Mosher, used corner, no accessories.
May 1882, E.Mosher, used corner, no accessories.
07-15-1901, W.S.Merrill, used corner, no accessories.
08-29-1904, W.S.Merrill, used corner, no accessories.
08-28-1975, J.L.Fletcher, used corner, no accessories.
12-03-1982, Farrier Surveying, Survey #6582, fd 1/2" iron rod, no accessories.
06-03-1988, Farrier Surveying, Survey #8388, fd 1/2"x3' gas pipe, w/ accessories.
06-07-1988, Farrier Surveying, Survey #8388, fd iron & cap#30079, no accessories.
06-10-1988, LCRC Liber 2 pg. 382.
May 1990, LCRC Liber ? pg. ? fd 1/2" pipe w/ accessories.
06-18-1990, E.D.Farrier, Survey #23089, fd 1/2"x3' Pipe w/ accessories.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *[Signature]*
Date 1-21-97

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-06: Cor. comn to Sec. 18, T26N-R6W, Oliver Township, & Sec. 13, T26N-R7W, Orange Township
Found 1/2"x18" R.B. w/ cap #30079 w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in centerline of Pierson Road falls of fence Occ. to East. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-06: Cor. comn to Sec. 18, T26N-R6W, Oliver Township, & Sec. 13, T26N-R7W, Orange Township
Found 1/2"x18" R.B. w/ cap #30079 w/ accessories. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in centerline of Pierson Road.
Set nail & tag S55E 6" Tw. Ironwood, 36.08'.
Set nail & tag S20E 11" Maple, 34.95' (old wit).
Set nail & tag S23W 7" Maple (triple), 59.34' (old wit).
Set nail & tag N25E 5" W. Birch, 43.35' (old wit).

igned by *Eugene Farrier*
urveyor's Michigan License No. 24594

Date 1-30-97

