

SURVEY & REMONUMENTATION

MAR 21 1997

KALKASKA COUNTY, MICHIGAN RECEIVED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 JAN 31 PM 2:26

For corners in

KALKASKA
(County)

Located in:

Corner Code #:

Joan Hall
REG. OF DEEDS

1996 REMONUMENTATION

1. Public Land Survey

T 26N R 6W

A-7

T 26N R 7W

(Handwritten mark)

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

1. EUGENE FARRIER, in a field survey on Nov. 21, 19 96

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-07: Cor. comn to Sec. 13 & 24, T26N-R7W, Orange Township, & Sec. 18 & 19, T26N-R6W, Oliver Township
1849, GLO resurvey, set post. 10" Sugar S19W 19, 10" Sugar N58W 24.
May 4, 1852, GLO resurvey, used corner. 20" Yellow Birch S38E 27, 10" Beech N70E 30.
Aug 10, 1880, G.A. Himpert, used corner, no accessories.
May 1882, E. Mosher, used corner, no accessories.
06-02-1902, W.S. Merrill, used corner, no accessories.
08-29-1904, W.S. Merrill, iron stake, no accessories.
08-27-1905, W.S. Merrill, used corner, no accessories.
05-17-1978, J.L. Wilcox, fd 1/2" rerod. Liber 2 pg. 299 in Survey.
May 1978, LCRC Liber 2 pg. 163
06-03-1988, Farrier Surveying, Survey #8388, fd 1/2" rerod, w/ accessories.
07-10-1988, LCRC Liber 2 pg. 382.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-07: Cor. comn to Sec. 13 & 24, T26N-R7W, Orange Township, & Sec. 18 & 19, T26N-R6W, Oliver Township
Found 5/8" x 24" iron. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box in c/l Pierson rd. & 1' North of c/l of Spencer rd. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accpeted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-07: Cor. comn to Sec. 13 & 24, T26N-R7W, Orange Township, & Sec. 18 & 19, T26N-R6W, Oliver Township
Found 5/8" x 24" iron. Pulled & Set 5/8" x 18" re-rod w/ Brass cap in mon box in c/l Pierson rd. & 1' North of c/l of Spencer rd.
N35W stop sign face 36.22'
S18E stop sign face 30.85'
Set nail & tag N45E cor. fence post 45.32'
Set nail & tag S24W 6" elm 96.95'

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman *(Signature)*
 Date 1-21-97



Signed by *(Signature)*
Surveyor's Michigan License-No. 24594

Date 1-30-97