

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Kalkaska</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>26N</u> R <u>7W</u>	C-2
	T <u>26N</u> R <u>7W</u>	A-1
	T <u>26N</u> R <u>7W</u>	B-1
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl F. Roser, in a field survey on May 12, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

C. Continued:

~~A. Description of original monument and accessories and/or subsequent restoration~~

B-1

Drove 5/8" x 18" rerod w/RLS cap		
10" Maple	N24°E	91.86'
Power Pole	N74°W	126.12'
7" Red Pine	S28°W	48.47'
S 1/4 Cor Sec 31		
(T27N-R7W) fd.		
1/2" rod	S89°52'51"E	75.46'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 - E 1/4 of Section 6; found 1" pipe per two W.S. Merrill 1905 wits. (Pine 40" N37°E, 25 links, fd. stp.; Pine 30" S55°W, 13 links, found stp. remains) Note, this pipe set by KJO from Merrills N.B.T.s in 1963. Corner in E'ly wheel track N-S sandtrail & in line w/old fns. West & East. Corner also fd., used & wit. by C. Hughes, LS w/Gosling-Czubak; Section 5 Survey.

A-1 - Fd. & accepted 3/4" pipe for NW corner of Section 6, T26N-R7W (four twp. cor. - Cor. common to T26 & 27N-R7 & 8W). Fits wits. & survey data by RLS's Verba, Nelson, Farrier, DelaMater, and K. Ostling in 1963 (now retired).

B-1 - Resotred N 1/4 corner of Section 6 (T26N-R7W) on line between fd. SW corner of Section 31 & fd. S 1/4 of Section 31 (T27N-R7W) & at prorated distance to 1849 G.L.O. Survey (G.L.O. plat) between fd. NE & NW corners of Section 6 (run-out section). Corner falls 1.2' south of ctr. of E-W B. Top road. A N-S (irregular) fence, looking south, is 16.5' east. Found 1" pipe (in B. top road), N87°39'W, 91.2'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>C-2</u>		<u>A-1</u>	
Found 1" pipe (buried 4")		Found 3/4" pipe	
*Pine stp. 40"	N37°E 16.2'±	4" Norway Pine	S10°W 38.64'
5" Maple	S42°W 27.5'	9" Maple	N36°E 46.72'
11" Cherry	N34°W 21.0'	Power Pole	S02°W 22.69
20" Maple	N45°E 59.7'	Fd. 3/4" pipe	S66°W 6.27'
Set cedar post w/loc tag	West 16 1/2'	Set cedar post w/loc tag	North 38'
		Ctr E-W B. top rd. is	5.2' North

* = W.S. Merrill 1905 wits.

Signed by Carl F. Roser 8-20-87 Date _____

Surveyor's Michigan License No. 12028

