

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY | T. <u>26</u> N. <u>7</u> W. | <u>F-10; G-10</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>28</u> | T. <u>26</u> N. <u>7</u> W. | <u>5; 4</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ E. _____ S. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 19, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

- 4
- Drove 5/8"x36" re-rod w/plastic DNR cap & cedar post w/loc. tag
 - 9" Oak N53°E 11.15'
 - 8" Maple S73°E 27.45'
 - 10" Oak S31°E 35.83'
 - Drove 5/8"x36" re-rod w/plastic DNR cap & cedar post at edge of lake S00°04'E 96.84

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-10 Established center of Sec. 28 at intersection of 1/4 lines. Drove pipe in lake. Water's edge (east shore of lake) is East 43'+.
- G-10 Reestablished E 1/4 corner Sec. 28, equidistant & on line between Sec. corners to N & S. Restoration by this method fits U.S. tie of 5 chains to pond to N (& over pond) exactly.
- 5 Established NE corner of SE 1/4 of NW 1/4 of Sec. 28 per standard B.L.M. instructions, based on controlling corner's around entire Sec. 28.
- 4 Established center of NW 1/4 of Sec. 28 per standard B.L.M. instructions, based on controlling corners around entire Sec. 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| F-10 | G-10 | 5 |
|--|---------------------------|---|
| Drove 1 1/4"x6' pipe | Set DNR mon. & cedar post | Drove 5/8"x36" rerod w/plastic DNR cap & ced. post w/loc. tag |
| 14" R. Pine N89°E 205.80 | 16" Oak S85°E 45.58 | 12" W. Pine N14°E 26.40 |
| 14" R. Pine S64°E 192.12 | 16" Oak S44°W 42.72 | 14" W. Pine N59°W 34.98 |
| Drove 1/2" bar & cedar post w/loc. tag N89°05'E 173.17 | 12" Oak N87°W 65.40 | 12" R. Pine S87°W 79.74 |
| | 6" Oak N55°W 35.77 | Fd. 1/2" rerod Cert. sur. RLS #16939 |
| | E-W fence remains | N24°02'W 2.73 |
| | Due N 25'+ | Fd. 1/2" rerod S16°14'E 42.74 |

SIGNED BY

Carl F. Roser

DATE

10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

ORANGE TOWNSHIP
KALKASKA COUNTY