

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located In: Corner Code #
 (County)
 1998 REMONUMENTATION
 1. Public Land Survey T.26N R.8W C-5
 T. R.
 T. R.
 T. R.
 2. Property Controlling S. T. R.
 in Section S. T. R.
 3. Miscellaneous S. T. R.
 Property in Sec. S. T. R.

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5			●										
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5: Sec. Cor. Common to Secs. 7, 8, 17 & 18, T26N-R8W, Boardman Township
 1852, GLO. Sub. Resurvey of Twsp., by V.W. Cankin DS., set post at corner; Y. Pine 16", S22°E, 62 Lks. (40.92'); W. Pine 24", N32°W, 1.05 Lks. (69.30')
 1918, Road Survey by W.S. Merrill CS., Co. Survey Bk. Pg. 51; notes finding old, witness stumps.
 1919, Sec. Sub. Survey by W.S. Merrill CS., FB # 19, Pg. 80; shows corner only
 1967, DNR mon. set corner by double proportional measurement
 1986, Certificate of Survey, N.B. DeYoung found DNR mon. w/acc., rec. in Liber 3, Pg. 36
 1990, E. Farrier, fd. DNR mon. LCRC Liber 2, Pg. 419

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5: Sec. Cor. Common to Secs. 7, 8, 17 & 18, T26N-R8W, Boardman Township
 Fd. & accepted DNR mon. as recorded in LCRC Liber 2, Pg. 419, 2' East of CL N-S rd. and 5' North of CL E-W rd, left in place
 N35°E, 57.45' - 12" J. Pine, found nail
 S25°W, 40.88' - 8" Oak, found nail
 S40°W, 6.20', found 3/4" iron pipe
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5: Sec. Cor. Common to Secs. 7, 8, 17 & 18, T26N-R8W, Boardman Township
 Fd. DNR mon. 2' East of CL N-S rd. and 5' North of CL E-W rd, left in place
 N35°E, 57.45' - 12" J. Pine, found nail
 S25°W, 40.88' - 8" Oak, found nail
 S40°W, 6.20', found 3/4" iron pipe
 N88°W, 79.86' - 12" R. Pine, set nail & washer



Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99 Surveyor's



Kalkaska County

REMON

9.00

3012688

Page: 1 of 1

02/10/1999 08:42A

LB: 5 PG: 343

ORS, JAN. 28, 1971
 SED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1993