

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)  
**1998 REMONUMENTATION**  
 1. Public Land Survey T 26N R 8W C-10  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
                                   T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section              S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous       S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Sec.      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

**FEB 22 1999**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on November 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**A. Description of original monument and accessories and/or subsequent restoration:**

C-10: 1/4 Cor. Common to Secs. 29 & 30, T26N-R8W, Boardman Township  
 1852, GLO. Sub. resurvey by V.W. Cankin D.S.; set corner; Beech 12" N37°W, 35 Lks. (23.10'); Sugar 24", S24°E, 43 Lks. (28.38')  
 1879, Road Survey by D.E. McVean CS. Co. Survey Bk. Pg. 35; found corner.  
 1903, Sec. Sub. Survey by W.S. Merrill CS. Co. Survey Bk., Pg. 33 & 34; shows corner only.  
 1903, 1905, Sec. Sub. Survey by W.S. Merrill CS. FB # 25, Pg. 74, Co. Survey Bk. Pg. 39.; shows corner only.  
 10-17-82, N.B. DeYoung, fd. 1/2" rod, Cert. of Survey  
 3-14-83, E. Farrier, set iron & cap #24594 by retracing Merrill's 1905 surveys in Secs. 29 & 30 (iron & cap #20705 set by N. DeYoung as 1/4 cor S16°E, 17.07') Cert. of Survey  
 3-14-83, E. Farrier, fd. iron & cap #24594, Cert. of Survey

**Ratified by Peer Group**  
**P.A. 345 - 1990 Kalkaska County**  
 Chairman Eugene Farrier  
 Date 2-2-99

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**


C-10: 1/4 Cor. Common to Secs. 29 & 30, T26N-R8W, Boardman Township  
 Fd. & accepted iron & cap #24594, 7' East of CL 2-Track & 20' West of old down N-S fence as shown in Cert. of Survey by E. Farrier (3-14-83). Pulled & set 5/8" X 36" re-rod W/ alum. cap.  
 S80°W, 61.15', 12" R. Pine, found spike  
 S16°E, 17.07' - found iron & cap #20705  
 No G.L.O. witnesses were found.  
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-10: 1/4 Cor. Common to Secs. 29 & 30, T26N-R8W, Boardman Township  
 Fd. & accepted iron & cap #24594, 7' East of CL 2-Track & 20' West of old down N-S fence. Pulled & set 5/8" X 36" re-rod W/ alum. cap.  
 East 33.05', found iron & cap, #28417  
 S70°E, 21.80' - 30" Maple, set nail & washer  
 S24°E, 39.56' - 30" Maple, set nail & washer  
 S80°W, 61.15', 12" R. Pine, found spike  
 S16°E, 17.07' - found iron & cap #20705

Signed by Eugene Farrier  
 Michigan License No. 24594

Date 2-8-99



**3012693**  
 Page: 1 of 1  
 02/10/1999 08:45A  
 LB: 5 PG: 348

REVISORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983  
 REVISED OCT., 1995