

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1998 REMONUMENTATION		
1. Public Land Survey	T. <u>26N</u> R. <u>8W</u>	<u>C-11</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Property Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Sec.	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____

**SURVEY &
REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on October 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11: Sec. Cor. Common to Secs. 29, 30, 31 & 32, T26N-R8W, Boardman Township
1852, G.L.O. Sub. resurvey by V.W. Cankin D.S.; set post for corner; Sugar 24", N15°E, 31 Lks. (20.46'); Beech 9", S25°W, 3 Lks. (1.98')
1879, Road Survey by D.E. McVean CS. Co. Survey Bk. Pg. 35, found corner.
1903, Sec. Sub. Survey by W.S. Merrill CS. Co. Survey Bk. Pg. 33 & 34, stone at corner.
1905, 1907, Sec. Sub. Survey by W.S. Merrill CS. Co. Survey Bk., Pg. 39 & 41; found stone buried, and set new stone on top, bringing it up to grade of road; Maple 12", N16°E, 1.23 1/2 Lks. (81.51')
12-16-74, J. Wilcox, fd. 1/2" iron LCRC, Liber 1, Pg. 335
12-16-74, J. Wilcox, shows witnesses only Liber 1, Pg. 621, Cert. of Survey
8-7-75, J. Wilcox, fd 1/2" iron, Liber 1, Pg. 685, Cert. of Survey
1-22-81, E. Farrier, shows cor. only, Cert. of Survey
12-5-81, E. Farrier, shows cor. only, Cert. of Survey
9-17-82, N. DeYoung, fd 1/2" iron, Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


C-11: Sec. Cor. Common to Secs. 29, 30, 31 & 32, T26N-R8W, Boardman Township
Fd. & accepted 1/2" X 36" iron 3' West of centerline 2-track to North, 3' East of extended centerline to South & 8' South of extended centerline to East, also falls 6' North of old fence mound to West (recorded in LCRC Liber 1, Pg. 335 and prev. Cert. of Surveys).
Pulled & set 5/8" X 36" re-rod w/ brass cap
N70°W, 27.09'- 10" Locust, fd. nail
N25°W, 24.63'- 12" Locust, fd. nail
No G.L.O. witnesses were found.
Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11: Sec. Cor. Common to Secs. 29, 30, 31 & 32, T26N-R8W, Boardman Township
Fd. & accepted 1/2" X 36" iron 3' West of centerline 2-track to North, 3' East of extended centerline to South & 8' South of extended centerline to East, also falls 6' North of old fence mound to West (recorded in LCRC Liber 1, Pg. 335 and prev. Cert. of Surveys).
Pulled & set 5/8" X 36" re-rod w/brass cap
S54°W, 47.11'-40" Maple, set nail & washer
N70°W, 27.09'- 10" Locust, fd. nail
N25°W, 24.63'- 12" Locust, fd. nail
N40°E, 29.82'- 14" Locust, set nail & washer

Signed by Eugene Farrier
Michigan License No. 24594

Date 2-8-99



3012694
Page: 1 of 1
02/10/1999 08:45A