

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1998 REMONUMENTATION	T <u>26N</u> R <u>8W</u>	<u>D-5</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &
REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5				●								
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-5: 1/4 Cor. Common to Secs. 8 & 17, T26N-R8W, Boardman Township
 1852, G.L.O. Sub. resurvey by V.W. Cankin D.S.; set corner; Elm 10", S1°E, 78 Lks. (51.48'); W. Pine 18", S37°W, 95 Lks. (62.70'); stream 40 Lks. C. NW. East, 1.22 Ch. (80.5')
 1967, DNR set DNR mon. at M.P.O.L.
 1986, N.B. DeYoung, set 1/2" iron & cap #20705 M.P.O.L., Cert. of Survey recorded in Lib. 3, Pg. 36, used two of the DNR witnesses

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5: 1/4 Cor. Common to Secs. 8 & 17, T26N-R8W, Boardman Township
 Fd. and accepted iron & cap #20705 set M.P.O.L., 8' South of CL foot path & 90' West of CL river. Pulled & reset 5/8" X 36" re-rod w/aluminum cap
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5: 1/4 Cor. Common to Secs. 8 & 17, T26N-R8W, Boardman Township
 Fd. and accepted iron & cap #20705 set M.P.O.L., 8' South of CL foot path & 90' West of CL river. Pulled & reset 5/8" X 36" re-rod w/aluminum cap
 N26°W, 32.18' - 24" W. Pine, set nail & washer
 S57°E, 18.58' - 12" W. Pine, set nail & washer
 S05°, 10.68' - 12" Maple, set nail & washer
 S60°W, 29.10' - 32" W. Pine, set nail & washer



Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99 Surveyor

3012697
 Page: 1 of 1
 02/10/1999 08:47
 LB: 5 PG: 352

