

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located In: Corner Code #
 (County)
 1998 REMONUMENTATION
 1. Public Land Survey T 26N R 8W D-7
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on October 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-7: 1/4 Cor. Common to Secs. 17 & 20, T26N-R8W, Boardman Township
 1852, GLO. Sub. resurvey by V.W. Cankin D.S.; set corner; Beech 8" N41°E, 48 Lks. (31.66'); Beech 8", S20°W, 20 Lks. (13.20')
 1879, Road Survey by D.E. McVean CS. Co. Survey Bk., Pg. 35; found corner
 9-1967, DNR set 1/2" X 12" bar in centerline East-West road, on line with old fence North & centerline old grade South
 8-29-78, J. Fletcher fd. 1/2" rod w/acc. LCRC rec. in Lib. 2, Pg. 135
 7-3-86, N.B. DeYoung, fd. DNR mon. w/acc. rec. in Lib. 3, Pg. 36
 8-9-94, E. Farrier fd. 1/2" iron w/acc., Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7: 1/4 Cor. Common to Secs. 17 & 20, T26N-R8W, Boardman Township
 Fd. and accepted 1/2" iron in CL Boardman Road and 4' East CL Quarterline Rd (as recorded in LCRC, Liber 2, Pg. 135) Pulled & set 5/8" X 18" re-rod w/brass cap in mon. box
 No G.L.O. witnesses found.

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7: 1/4 Cor. Common to Secs. 17 & 20, T26N-R8W, Boardman Township
 Fd. and accepted 1/2" iron in CL Boardman Road and 4' East CL Quarterline Rd. Pulled & set 5/8" X 18" re-rod w/brass cap in mon. box
 S45°W, 92.85' - 10" J. Pine, set nail & washer
 S50°E, 55.37' - Wood post riser (telephone), set nail & washer
 N45°E, 48.55' - Power pole, set nail & washer
 South 27.97' - 3" steel fence post (face)



Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99

Surveyor's

3012698
 Page: 1 of 1
 02/10/1999 08:47A



Kalkaska County REMON 9.00 LB: 5 PG: 353