

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located In: _____ Corner Code # _____
 (County)
 1998 REMONUMENTATION
 1. Public Land Survey T 26N R 8W D-13 ✓
 T 25N R 8W D-1
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13: 1/4 Cor. Common to Sec. 32, T26N-R8W, Boardman Township & D-1: 1/4 Cor. Sec. 3, T25N-R8W.

1852, GLO. Twp. Lines Resurvey by V.W. Cankin, D.S.; set corner, Beech 12", N50°E, 68 Lks. (44.88'); Beech 16", N3.5°W, 64 Lks. (42.24')

1905, Sec. Sub. Survey by W.S. Merrill CS., Co. Survey Bk. Pg. 39; notes stone at corner.

12-22-75, L. Czubak, set 5/8" iron & cap, Liber 1, Pg. 799, Cert. of Survey

12-22-75, L. Czubak, set 5/8" iron & cap, Liber 1, Pg. 797, Cert. of Survey

12-22-75, L. Czubak, set 5/8" iron & cap, Liber 1, Pg. 795, Cert. of Survey

12-22-75, L. Czubak, set 5/8" iron & cap, Liber 1, Pg. 793, Cert. of Survey

12-22-75, L. Czubak, set 5/8" iron & cap, Liber 1, Pg. 791, Cert. of Survey

12-22-75, L. Czubak, set 5/8" iron & cap, Liber 1, Pg. 789, Cert. of Survey

7-22-98, R. Mitchell, fd. 5/8" iron & cap #12581, Cert. of Survey

**Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County**

Chairman Eugene Farrier

Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13: 1/4 Cor. Common to Sec. 32, T26N-R8W, Boardman Township & D-1: 1/4 Cor. Sec. 3, T25N-R8W.

Found & accepted 5/8" iron & cap #12581, 5' North of centerline of road (as recorded in prev. Cert. of Surveys) Added brass cap.

N48°W, 75.30'- power pole, found nail

No G.L.O. witnesses were found.

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13: 1/4 Cor. Common to Sec. 32, T26N-R8W, Boardman Township & D-1: 1/4 Cor.

Found & accepted 5/8" iron & cap #12581, 5' North of centerline of road (as recorded in prev. Cert. of Surveys) Added brass cap.

North 33.03'- iron & cap #31611

N65°E, a 34.75'- 40' Maple, set nail & washer

S50°E, 67.67'- power pole, set nail & washer

N48°W, 75.30'- power pole, found nail

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99

