

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located In: Corner Code #
 (County)
 1998 REMONUMENTATION
 1. Public Land Survey T 26N R 8W E-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, EUGENE FARRIER, in a field survey on November 4, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8: 1/4 Cor. Common to Secs. 20 & 21, T26N-R8W, Boardman Township
 1852, GLO. Sub. resurvey by V.W. Cankin D.S.; set corner; Hemlock 24", S70°W, 10 Lks. (6.60'); Beech 8", N8°E, 41 Lks. (27.06')
 1879, Road Survey By D.E. McVean CS. Co. Survey Bk. Pg. 35; found corner.
 1948, Parcel Survey by (unknown) Co. Survey Bk. Pg. 54; R.R. rail at corner.
 7-12-73, P. Perla, fd. R.R. rail, Lib. 1, Pg. 326, Cert. of Survey
 10-2-73, P. Perla, shows cor. only, Raudman's Terrace
 4-8-75, J. Wilcox, fd. R.R. rail, Lib. 1, Pg. 649, Cert. of Survey
 8-16-78, J. Fletcher, fd. R.R. iron, LCRC Lib. 2, Pg. 113
 8-19-81, E. Farrier, fd. R.R. iron, Lib. 2, Pg. Cert. of Survey
 8-19-81, E. Farrier, fd. R.R. iron, Cert. of Survey
 8-22-89, J. Wilcox, fd. plow pt (fits witnesses to R.R. rail) Lib. 3, Pg. 413, Cert. of Survey
 2-17-93, E. Farrier, fd. R.R. iron, Lib. 4, Pg. 126, Cert. of Survey
 8-9-94, E. Farrier, fd. R.R. iron, Cert. of Survey
 4-20-98, E. Farrier, shows cor. only, Cert. of Survey
 6-5-98, E. Farrier, shows cor. only, Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8: 1/4 Cor. Common to Secs. 20 & 21, T26N-R8W, Boardman Township
 Fd. & accepted R.R. rail 1' East of CL rd. and 3' South of fence to West (as rec. in LCRC, Lib. 2, Pg. 113, & previous cert. of surveys)
 Added 5/8" x 18" re-bar w/brass cap
 N40°E, 60.32' - 12" R. Pine, found nail
 N88°W, 31.61' - Wood corner fence post, found nail
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group Accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8: 1/4 Cor. Common to Secs. 20 & 21, T26N-R8W, Boardman Township
 Fd. & accepted R.R. rail 1' East of CL rd. and 3' South of fence to West. Added 5/8" x 18" re-bar w/brass cap
 N40°E, 60.32' - 12" R. Pine, found nail
 N65°E, 39.20' - 10" R. Pine, set nail & washer
 S50°W, 41.53' - Wood gate post (North), set nail & washer
 N88°W, 31.61' - Wood corner fence post, found nail

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99



Kalkaska County REMON 9.00 LB: 5 PG: 360

3012705
 Page: 1 of 1
 02/10/1999 08:51A

REVISIONS
 REVISION 14.18
 REVISION 14.18
 REVISION OCT., 15