

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located in: _____ Corner Code # _____
 (County)
1998 REMONUMENTATION
 1. Public Land Survey T 26N R 8W E-12
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on October 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12: 1/4 Cor. Common to Secs. 32 & 33, T26N-R8W, Boardman Township
 1852, G.L.O. Sub. Resurvey of Twp., by V.W. Cankin, D.S.; set corner; Sugar 24", N80°E, 34 Lks. (22.44'); Beech 8", S76°W, 27 Lks. (17.82')
 1898, Sec. Sub. Survey by E. Mosher CS., FB # 32, Pg. 82; shows establishing corner. M.O.L.
 1901, Sec. Sub. Survey by W.S. Merrill CS., Co. Survey Bk, Pg. 4 & 29; stone at corner.
 11-3-86, R. Mitchell, fd. 3/4" iron bar, LCRC in Liber 2, Pg. 313

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12: 1/4 Cor. Common to Secs. 32 & 33, T26N-R8W, Boardman Township
 Fd. 3/4" re-rod 6' West of centerline rod on fence to East & West (as reorded in LCRC, Liber 2, Pg. 313) Pulled & set 5/8" X 18" re-rod w/brass cap
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12: 1/4 Cor. Common to Secs. 32 & 33, T26N-R8W, Boardman Township
 Fd. 3/4" re-rod 6' West of centerline rod on fence to East & West (as reorded in LCRC, Liber 2, Pg. 313) Pulled & set 5/8" X 18" re-rod w/brass cap
 N35°E, 50.59'- 5" Ash, set nail
 S75°E, 26.60'- 40" Twin Maple, set nail & washer
 S52°E, 46.31' - 10" R. Pine, fd. nail
 S12°W, 76.78'- 30" Twin Maple, fd. nail

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99

