

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1998 REMONUMENTATION		
1. Public Land Survey	T. <u>26N</u> R. <u>8W</u>	<u>G-7</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Property Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Sec.	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____

SURVEY & REMONUMENTATION

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

I, EUGENE FARRIER, in a field survey on October 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-7 Sec. Cor. Common to Secs. 15, 16, 21, & 22, T26N-R8W, Boardman Township
 1852, GLO. Sub. resurvey by V.W. Cankin D.S.; set post at corner; Y. Birch 10", N34°E, 27 Lks. (17.82'); Beech 8", S56°W, 52 Lks. (34.32')
 1882, Road Survey by E. Mosher S. Co. Survey Bk. Pg. 36; found corner.
 1902, 1907, 1909, Sec. Sub. & parcel Surveys by W.S. Merrill CS., FB # 4, Pg. 67, FB # 22, Pg. 141 & FB # 23, Pg. 130; shows finding corner only.
 1948, Parcel Survey by (Unknown) Co. Survey Bk. Pg. 54; shows corner only.
 2-8-73, P. Perla set 1/2" iron & cap, West 16.02' R.R. spike; 36" Beech N05°W, 34.82'; 24" Maple, N80°E, 133.13'; 6" Cherry, S05°W, 40.83' rec. in Liber 1, Pg. 273, Certificate of Survey.
 1-28-74, L. Czubak, set 1/2" iron & cap from evidence of surveys and occupation, West 16.02' R.R. spike; 36" Beech N05°W, 34.82'; 24" Maple, N80°E, 133.13'; 6" Cherry, S05°W, 40.83'. LCRC in Liber 1, Pg. 328.
 5-1-75, L. Czubak, fd. 1/2" iron w/cap #12581, Liber 1, Pg. 655, Cert. of Survey
 9-18-78, C. Roser, fd. iron & cap #12581, LCRC in Liber 2, Pg. 120
 4-21-88, E. Farrier, fd. 1/2" iron & cap, LCRC in Liber 2, Pg. 383
 7-12-91, E. Farrier, fd. 1/2" iron & cap, Liber 4, Pg. 148, Cert. of Survey
 2-17-93, E. Farrier, fd. 1/2" iron & cap, Liber 4, Pg. 126, Cert. of Survey
 5-18-93, E. Farrier, fd. 1/2" iron & cap, Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G-7 Sec. Cor. Common to Secs. 15, 16, 21, & 22, T26N-R8W, Boardman Township
 Fd. & accepted 1/2" iron & cap #12581, 1.5' North of CL road, and previous Cert. of Surveys. Pulled and set 5/8" X 18" re-bar w/brass cap in mon. box.
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 Sec. Cor. Common to Secs. 15, 16, 21, & 22, T26N-R8W, Boardman Township
 Found & accepted 1/2" iron & cap # 12581, 1.5' North of CL road. Pulled and set 5/8" X 18" re-bar w/brass cap in mon. box.
 N50°W, 46.28' - 4" Ash, set nail & washer
 North, 27.29' - 5" Twin Birch, set nail & washer
 S17°E, 65.20' - 8" Twin Maple, set nail & washer
 S03°W, 41.03' - 12" Cherry, set nail & washer

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99



3012718
 Page: 1 of 1
 02/10/1999 09:01A

REVISIONS: JAN. 28, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983
 REVISED OCT., 1991

