

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|------------------------------------|--------------------------|---------------|
| <u>KALKASKA</u> | Located In: | Corner Code # |
| (County) | | |
| 1998 REMONUMENTATION | | |
| 1. Public Land Survey | T <u>26N</u> R <u>8W</u> | <u>G-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

SURVEY & REMONUMENTATION

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9: Sec. Cor. Common to Secs. 21, 22, 27 & 28, T26N-R8W, Boardman Township
 1852, GLO. Sub. resurvey by V.W. Cankin D.S.; set post at corner; Hemlock 18", S40°2, 33 Lks. (21.78') Hemlock 20", N22°E, 21 Lks. (13.86') stream 12 Lks. C. NW., North, 7.75 Chs. (511.5')
 1882, Road Survey by E. Mosher CS., Co. Survey Bk. Pg. 36; found corner.
 1900, 1902, 1915, Sec. Sub. Survey by W.S. Merrill CS., FB # 19, Pg. 66, Co. Survey Bk. Pg. 12, 59 & 50; shows corner only.
 1948, Parcel Survey by (Unknown) Co. Survey Bk. Pg. 54; shows corner only.
 10-30-74, L. Czubak set iron & cap #12581 from Mosher notes July, 31, 1882, LCRC, Lib. 1, Pg. 329
 8-27-79, J. Wilcox, fd. iron, Lib. 2, Pg. 517, Cert. of Survey
 7-23-90, E. Farrier, fd. iron & cap #12581, Cert. of Survey
 2-11-93, E. Farrier, fd. iron & cap #12581, Cert. of Survey
 2-17-93, E. Farrier, fd. iron & cap #12581, Liber 4, Pg. 126, Cert. of Survey
 7-16-96, E. Farrier, fd. iron & cap #12581, Cert. of Survey
 12-24-96, E. Farrier, fd. iron & cap #12581, Cert. of Survey
 7-16-98, E. Farrier, fd. iron & cap #12581, Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9: Sec. Cor. Common to Secs. 21, 22, 27 & 28, T26N-R8W, Boardman Township
 Fd. & accepted 5/8" re-rod & cap #12581 in CL road (as recorded in LCRC Lib. 1, Pg. 329 and prev. recorded surveys) Added brass cap North 36.51', found 5/8" re-rod
 N25°E, 64.82' - 18" Twin Maple, found nail
 East 33.32', found 5/8" iron & cap #12581
 S54°E, 30.02' - 10" Balsam, found nail
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9: Sec. Cor. Common to Secs. 21, 22, 27 & 28, T26N-R8W, Boardman Township
 Fd. & accepted 5/8" re-rod & cap #12581 in CL road. Added brass cap.
 North 36.51', found 5/8" re-rod
 N25°E, 64.82' - 18" Twin Maple, found nail
 East 33.32', found 5/8" iron & cap #12581
 S54°E, 30.02' - 10" Balsam, found nail



Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99



3012720
 Page: 1 of 1
 02/10/1999 09:02A
 Kalkaska County REMON 9.00 LB: 5 PG: 375