

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1998 REMONUMENTATION		
1. Public Land Survey	T <u>26N</u> R <u>8W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on October 29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7: 1/4 Cor. Common to Secs. 15 & 22, T26N-R8W, Boardman Township
 1852, GLO. Sub. resurvey by V.W. Cankin D.S.; set corner; Beech 10", N40°W, 23 Lks. (15.18'); Beech 14", S44°E, 25 Lks. (16.50')
 1909, Sec. Sub. Survey by W.S. Merrill CS., FB # 23, Pg. 130; shows corner only.
 7-15-77, L. Dragoo, iron rod Liber 2, Pg. 28
 9-18-78, C. Roser fd. & accepted P-K nail in CL of E-W B. Top rd & in line w/old fence remains to South. Fits Mosher survey of 1888.
 Replaced w/ 5/8" X 18" re-rod w/ cap #12028, LCRC in Lib. 2, Pg. 122.
 4-21-88, E. Farrier, fd. iron & cap #12028, LCRC in Lib. 2, Pg. 383
 4-25-88, E. Farrier, Fd. iron & cap #12028, Cert. of Survey
 12-11-90, E. Farrier, fd. iron & cap #12028, Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7: 1/4 Cor. Common to Secs. 15 & 22, T26N-R8W, Boardman Township
 Fd. & accepted 5/8" iron & cap #12028, 1' South of CL rd. on tree line to South (as recorded in LCRC's & previous Cert. of Surveys)
 Added brass cap & mon. box
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7: 1/4 Cor. Common to Secs. 15 & 22, T26N-R8W, Boardman Township
 Fd. & accepted 5/8" iron & cap #12028, 1' South of CL rd. on tree line to South. Added brass cap & mon. box
 N03°W, 36.03' - Wood guard post (telephone), set nail & washer
 S60°E, 79.15' - r.r. tie guard post, set nail & washer
 South 59.59' - 10' Locust, set nail & washer
 S44°W, 71.63' - 12" W. Pine, set nail & washer



Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 2-8-99



3012726
 Page: 1 of 1
 02/10/1999 09:06A