

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located In: _____ Corner Code # _____
 (County)
 1998 REMONUMENTATION
 1. Public Land Survey T.26N R.8W H-13
 T.25N R.8W H-1
 T. _____ R. _____
 T. _____ R. _____
 2. Property Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Sec. S. _____ T. _____ R. _____

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-13: 1/4 Cor. Common to Sec. 34, T26N-R8W, Boardman Township, & H-1: 1/4 Cor. Sec. 5, T25N-R8W.

1852, GLO. Twp. Line Resurvey by V.W. Cankin D.S.; set post for cor., Hemlock 22", N32°E, 14 Lk. (9.24'); Hemlock 6", N59°W, 33 Lk. (21.78').

- 1-30-74, J. Fletcher, set 1/2" re-rod by single proportionate measurement. LCRC Liber 1, Pg. 291
- 1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 465, Cert. of Survey
- 1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 466, Cert. of Survey
- 1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 468, Cert. of Survey
- 1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 469, Cert. of Survey
- 1-30-74, J. Fletcher, shows cor. only, Liber 1, Pg. 470, Cert. of Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13: 1/4 Cor. Common to Sec. 34, T26N-R8W, Boardman Township, & H-1: 1/4 Cor. Sec. 5, T25N-R8W.

Found & accepted iron & cap #19830 in centerline road East extended, and on fence to South (as recorded in LCRC, Liber 1, Pg. 291, an previous Cert. of Surveys)

No G.L.O. witnesses were found.

Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13: 1/4 Cor. Common to Sec. 34, T26N-R8W, Boardman Township, & H-1: 1/4 Cor. Sec. 5, T25N-R8W.

Found & accepted iron & cap #19830 in centerline road East extended, and on fence to South (as recorded in LCRC, Liber 1, Pg. 291, an previous Cert. of Surveys) Pulled and set 5/8" X 1 1/2" re-rod w/ brass cap.

- North 33.13'- iron & cap #19830
- N71°E, 39.23'- 12" W. Pine, set nail & washer
- S12°E, 33.92'- Wood fence post, set nail & washer
- S55°W, 60.12' - 14" Red Pine, set nail & washer

Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99



3012729
 Page: 1 of 1
 02/10/1999 09:09A

